

Contents

Page

Foreword	vii
14.6 Hydraulic performance acceptance tests	1
14.6.1 Introduction	1
14.6.1.1 Purpose	1
14.6.1.2 Scope	1
14.6.1.3 Terms and definitions	2
14.6.2 Factory performance tests	10
14.6.2.1 General	10
14.6.2.2 Nonwitnessed pump test	10
14.6.2.3 Witnessed pump test	10
14.6.3 Pump acceptance tests	10
14.6.3.1 General	10
14.6.3.2 Guarantees	11
14.6.3.3 Measurement uncertainty	12
14.6.3.4 Performance test acceptance grades and tolerances	14
14.6.4 Default test acceptance grades	18
14.6.5 Test procedures	19
14.6.5.1 General	19
14.6.5.2 Date of testing	19
14.6.5.3 Test procedure	19
14.6.5.4 Testing equipment	19
14.6.5.5 Records and report	19
14.6.5.6 Test arrangements	19
14.6.5.7 Test conditions	20
14.6.5.8 NPSH tests	20
14.6.6 Analysis	21
14.6.6.1 Translation of the test results to the guarantee conditions	21
14.6.6.2 Obtaining specified characteristics	23
Appendix A Test arrangements (normative)	25
A.1 General	25
A.2 Measurement principles	25
A.3 Various measurement methods	26
A.4 Simulated test arrangements	31
A.5 Pumps tested with fittings	32
A.6 Pumping installation under submerged conditions	32
A.7 Self-priming pumps	35
A.8 Friction losses at inlet and outlet	35
Appendix B Hydrostatic pressure testing (normative)	38
B.1 Purpose and scope	38
B.2 Definitions	38
B.3 General	38
B.4 Timing of the test	38
B.5 Preparation for testing	39
B.6 Test liquid	39
B.7 Test pressure	39

B.8	Test procedure	39
B.9	Acceptance criteria	40
B.10	Repairs	40
B.11	Test records	40
B.12	Test certificate.	41
B.13	Test report.	41
Appendix C	Purpose of test tolerances (informative)	42
C.1	Explanation of test tolerances - variations	42
C.2	Manufacturing variations.	42
C.3	Effect of accessories on mechanical losses (power)	43
C.4	Selection of pump test acceptance grades and corresponding tolerance bands	43
Appendix D	Recommended tests (informative)	44
D.1	General	44
D.2	Recommended test specification matrix	45
Appendix E	Mechanical test (informative)	46
E.1	Mechanical test objective	46
E.2	Mechanical test setup	46
E.3	Mechanical test operating conditions	46
E.4	Mechanical test instrumentation	46
E.5	Mechanical test procedure	47
E.6	Mechanical test acceptance criteria	47
E.7	Mechanical test records	48
Appendix F	NPSH test arrangements (informative).	49
F.1	General	49
F.2	Characteristics of the circuit	49
F.3	Characteristics of the test liquid	49
F.4	Allowable air content during NPSH testing	49
F.5	Determination of the vapor pressure.	50
F.6	Example of test arrangements	51
Appendix G	Tests performed on the entire equipment set - string test (informative)	54
Appendix H	Reporting of test results (informative).	56
H.1	Performance test report	56
Appendix I	Measurement equipment (informative).	60
I.1	Head measuring apparatus.	60
I.2	Measurement of rotating speed	60
I.3	Measurement of flow rate	61
I.4	Measurement of pump power input	63
I.5	Special cases	63
I.6	Determination of motor pump unit overall efficiency.	64
Appendix J	Suitable time periods for calibration of test instruments (informative)	65
J.1	Recalibration interval	65
Appendix K	Special test methods (informative)	66
K.1	General	66
K.2	Model tests for pump acceptance.	66

Appendix L	Determination, application, and calculation of instrument (systematic) uncertainty (informative)	72
L.1	Determination, application, and calculation of instrument (systematic) uncertainty	72
L.2	Distribution of probability.	73
L.3	Examples of measurement uncertainty calculations.	74
Appendix M	Unit conversions (informative)	84
Appendix N	References (informative).	86
Appendix O	Index	89

Figures

14.6.1.3	— Datum elevation for various pump designs at eye of first-stage impeller	8
14.6.3.4.2a	— Unilateral tolerance acceptance	16
14.6.3.4.2b	— Bilateral tolerance acceptance	16
14.6.3.4.3a	— Tolerance field for acceptance grades 1U and 2U	17
14.6.3.4.3b	— Tolerance field for acceptance grade 1E	17
14.6.3.4.3c	— Tolerance field for acceptance grades 1B, 2B, and 3B	17
A.1	— Determination of the pump total head (isometric illustration)	27
A.2	— Flow at suction at part load	28
A.3	— Error in measurement of $H(Q)$ depending on distance of suction pressure gauge from impeller	28
A.4	— Correction of suction pressure for suction recirculation	29
A.5	— Pressure tapping perpendicular to the plane of the volute or to the plane of a bend, respectively.	29
A.6	— Requirements for static pressure tapplings	30
A.7	— Four pressure tapplings connected by a ring manifold (grade 1).	30
A.8	— One pressure tapping (general for grade 2 and 3)	30
A.9	— Bowl assembly total head determination for vertically suspended pumps	33
A.10	— Determination of pump head.	36
A.11	— Bowl assembly total head determination for vertically suspended pump with a closed suction	37
F.1	— Air separating at the pump suction nozzle as a function of NPSHA if the pump draws cold water from a tank with air-saturated water. Air pressure above tank equal to atmospheric pressure.	50
F.2	— Variation of NPSHA in a closed loop by head and/or temperature controlled.	52
F.3	— Variation of NPSHA by control of liquid level at pump inlet sump.	53
F.4	— Variation of NPSHA by means of an inlet throttle valve	53
H.1	— Sample pump test curve	57
H.2	— Example test sheet	59
I.1	— Arrangement for determination of reference plane of spring pressure gauges	60
L.1	— Output signal vs. pressure value	81

Tables

14.6.1.3a	— List of quantities	2
14.6.1.3b	— Alphabetical list of basic letters used as symbols	9
14.6.1.3c	— List of letters and numbers used as subscripts	9

14.6.3.3.2 — Permissible amplitude of fluctuation as a percentage of mean value of quantity being measured	12
14.6.3.3.3 — Maximum permissible measurement device uncertainty at guarantee point	13
14.6.3.4 — Pump test acceptance grades and corresponding tolerance band	14
14.6.4 — Default acceptance grade based on purchaser's intended service	18
14.6.5.8.2.1 — Methods of determining NPSH3	22
B.1 — Requirements for longer test periods	40
D.1 — Matrix of recommended tests	45
G.1 — Influencing factors for calculating pump efficiency for different configurations.	55
J.1 — Instrument recalibration intervals.	65
L.1 — Lab pressure calibrator calibration data	75
L.2 — Published accuracy of lab calibration devices.	75
L.3 — Lab precision DC current measurement device calibration data.	76
L.4 — Lab DC current source calibration data	76
L.5 — Pressure transducer calibration.	77
L.6 — DA system current measurement module (output) calibration data	77
L.7 — Calculation of percent uncertainty for the discharge pressure, full system of 300 psi pressure transducer and data acquisition system	79
L.8 — Differential pressure transducer information	80
L.9 — Signal measurement device information	80
L.10 — Venturi information - BIF 2-in s/n 12345	80
L.11 — Differential pressure transducer calibration data.	81
L.12 — Differential pressure transducer calibration data analysis.	81
L.13 — Venturi flowmeter calibration data and analysis	82
L.14 — Calculation of individual device uncertainty and total uncertainty	82
M.1 — Conversion factors	84